



No Fault SporTurf for Playgrounds
COMPACTED STONE BASE REQUIREMENTS

1. **DEPTH**
3" minimum thickness - to be determined by local soil conditions.
2. **SLOPE**
Stone elevation shall maintain slope to drains or toward low end. Base must exhibit positive drainage in all areas.
3. **COMPACTION**
Density requirement is 90% compaction with final condition of stone as level and stable so as not to shift when traveled on or during surface installation process.
4. **POROSITY**
Stone base course shall maintain porosity for direct drainage. Care must be taken not to choke off porosity.
5. **ENCLOSURE**
Stone base course shall be surrounded by a retaining curb or other form of enclosure, such as a sidewalk.
6. **DRAINAGE**
Subsurface drainage is recommended under and around a stone base. Perforated pipe or similar system is acceptable. Positive drainage in all areas is required.
7. **STONE SELECTION** (It is critical that the use of different stone sizes described below is strictly adhered to).
Stone shall be uniformly mixed in an approving pugmill or on a mixing table or by other mechanical means (such as quarry blending operations) prior to placement on the subgrade. Test samples will be taken after mixing, and the material shall conform to specified requirements prior to placement on the subgrade. The material shall be wetted during mixing operations if necessary for proper blending.
8. **STONE GRADATION**

<u>U.S. Sieve</u>	<u>Percent Passing</u>
1"	100
3/4"	90 - 100
No. 4	35 - 60
No. 30	10 - 30
No. 200	2 - 9
9. **NAILER BOARDS**
Install a 2x4 treated wood nailer boards around the perimeter of the enclosure. Although not required, Trex boards are recommended. Nailer board should be approximately 3/8" below the top of the surrounding enclosure (finished grade) with the stone base flush with the top of the nailer board.

NOTE: Although No Fault Sport Group shall advise owner and/or prime contractor if a deficiency in work-by-others is discovered, No Fault accepts no responsibility for work-by-others. It is the owner and/or prime contractor's responsibility to ensure the accuracy of work not executed by No Fault Sport Group. Prime Contractor and Owner agree to release No Fault Sport Group from responsibility to repair defects that are the result of defects in the base/subgrade.